

Appendix 4B-1: Annual Water Budgets for Treatment Cells in Stormwater Treatment Area 1-W

	Inflow ^{a, b}			Outflow				ΔS	r	ε
	I_s	I_g	P	Σ_{inflow}	O_s	O_g	ET			
Buffer Cell										
WY 95-96	256.4	-	0.7	257.0	224.3	7.4	0.7	232.4	0.10	24.5 9.5%
WY 96-97	177.7	-	0.8	178.5	149.8	7.6	0.7	158.1	-0.13	20.6 11.5%
WY 97-98	130.2	-	0.8	131.1	118.8	8.2	0.7	127.7	0.16	3.2 2.5%
WY 98-99	147.4	-	0.6	148.1	124.7	8.1	0.8	133.6	-0.29	14.8 10.0%
WY 99-00	-	-	-	-	-	-	-	-	-	-
WY 00-01	-	-	-	-	-	-	-	-	-	-
WY 01-02	-	-	-	-	-	-	-	-	-	-
TOTAL	711.7	-	2.9	714.6	617.5	31.3	2.9	651.7	-0.16	63.1 8.8%
	99.6%	-	0.4%		94.8%	4.8%	0.4%			
Treatment Cell 1										
WY 95-96	100.1	4.0	6.8	110.9	102.4	0.1	6.8	109.3	0.78	0.8 0.8%
WY 96-97	57.5	3.0	7.5	68.0	58.4	0.2	6.9	65.4	-0.94	3.5 5.1%
WY 97-98	41.5	6.1	7.8	55.4	43.0	0.0	6.5	49.6	1.18	4.7 8.4%
WY 98-99	47.5	3.6	6.3	57.4	52.2	0.5	7.7	60.4	-0.35	-2.6 -4.6%
WY 99-00	177.1	4.0	7.5	188.5	148.5	6.7	7.6	162.8	0.82	24.9 13.2%
WY 00-01	136.8	1.8	5.2	143.7	104.1	7.5	8.3	119.9	-2.30	26.1 18.1%
WY 01-02	157.2	2.8	7.8	167.8	180.3	6.3	7.8	194.4	0.93	-27.6 -16.4%
TOTAL	717.7	25.2	48.9	791.8	689.0	21.2	51.7	761.9	0.12	29.7 3.8%
	90.6%	3.2%	6.2%		90.4%	2.8%	6.8%			
Treatment Cell 2										
WY 95-96	124.2	-	5.3	129.5	116.1	22.4	5.3	143.8	0.48	-14.8 -11.4%
WY 96-97	92.3	-	5.9	98.2	89.9	22.8	5.4	118.1	-0.86	-19.0 -19.4%
WY 97-98	77.3	-	6.2	83.4	73.5	24.8	5.1	103.3	1.19	-21.1 -25.3%
WY 98-99	77.1	-	4.9	82.0	62.6	24.5	6.0	93.0	-0.59	-10.4 -12.7%
WY 99-00	73.0	-	5.5	78.5	70.9	23.8	5.4	100.1	0.62	-22.2 -28.4%
WY 00-01	44.8	-	3.7	48.5	47.8	20.5	5.9	74.2	-1.84	-23.9 -49.4%
WY 01-02	90.7	-	5.5	96.2	83.5	17.1	5.6	106.1	0.82	-10.6 -11.1%
TOTAL	579.4	-	37.0	616.3	544.2	155.7	38.7	738.6	-0.17	-122.1 -19.8%
	94.0%	-	6.0%		73.7%	21.1%	5.2%			
Treatment Cell 3										
WY 95-96	102.4	5.3	5.2	112.9	88.2	7.4	5.3	100.8	0.47	11.6 10.3%
WY 96-97	58.4	3.9	5.8	68.0	61.9	7.6	5.3	74.9	-0.41	-6.4 -9.5%
WY 97-98	43.0	7.9	6.0	56.9	35.7	8.1	5.0	48.8	0.58	7.5 13.2%
WY 98-99	59.4	4.7	4.8	68.9	52.4	8.6	5.9	66.9	-0.55	2.6 3.8%
WY 99-00	89.9	5.2	5.3	100.4	77.6	8.0	5.4	91.0	0.52	8.9 8.9%
WY 00-01	60.8	2.3	3.6	66.7	43.1	7.6	5.8	56.5	-0.96	11.2 16.8%
WY 01-02	89.6	3.6	5.4	98.6	37.3	6.4	5.5	49.2	0.50	48.9 49.6%
TOTAL	503.4	32.8	36.2	572.4	396.2	53.7	38.1	487.9	0.15	84.3 14.7%
	88.0%	5.7%	6.3%		81.2%	11.0%	7.8%			
Treatment Cell 4										
WY 95-96	116.1	-	1.9	117.9	110.0	8.4	1.9	120.3	0.14	-2.5 -2.1%
WY 96-97	89.9	-	2.1	92.0	83.4	8.5	1.9	93.9	-0.25	-1.6 -1.8%
WY 97-98	73.5	-	2.2	75.7	63.9	9.3	1.8	75.0	0.44	0.2 0.3%
WY 98-99	62.6	-	1.8	64.3	53.3	9.2	2.1	64.6	-0.20	0.0 -0.1%
WY 99-00	70.9	-	1.9	72.8	71.9	8.9	1.9	82.8	0.15	-10.1 -13.8%
WY 00-01	47.8	-	1.3	49.1	39.6	7.7	2.1	49.4	-0.53	0.3 0.7%
WY 01-02	83.5	-	2.0	85.4	76.3	6.4	2.0	84.6	0.28	0.5 0.6%
TOTAL	544.2	-	13.1	557.3	498.4	58.3	13.8	570.5	0.02	-13.2 -2.4%
	97.6%	-	2.4%		87.4%	10.2%	2.4%			

^a All water budget terms expressed as hm^3 ($= 1,000,000 m^3$). $1 hm^3 = 810.7$ ac-ft.

^b I_s = total surface water inflow; I_g = total groundwater inflow; P = precipitation; O_s = total surface water outflow; O_g = total groundwater outflow; ET = evapotranspiration; ΔS = change in storage volume; r = water budget residual; ε = water budget error.